

Maine Turnpike Authority

Contract
2008.05

Concrete Repair, Membrane and Paving Dutton Hill Road Bridge MM59.9, Route 122 Bridge MM74.0,
Route 197 Bridge MM93.3 and Gardiner Interchange Bridge MM 102.0

Item No.	Description	Quantity	Unit
202.202	Removing Pavement Surface	3,489.00	SY
206.082	Structural Earth Excavation - Major Structures	6.00	CY
403.21	Hot Bituminous Pavement, 9.5 MM	335.00	TON
409.15	Bituminous Tack Coat, Applied	62.00	Gal
419.30	Full Depth Bituminous Sawcut	472.00	LF
507.095	Aluminum Bridge Railing- Splice Modification	88.00	EA
508.145	High Performance Waterproofing Membrane	2,884.00	SY
515.201	Pigmented Protective Coating for Concrete Surfaces	1,529.00	SY
518.6313	Abutment and Bridge Seat Repairs	117.00	SF
518.6314	Pier Repairs	333.00	SF
518.6315	Fascia and Overhang Repairs	1,556.00	SF
518.64	Thoroc 10-60 - Rapid Set Mortar (50 lb. Bag)	24.00	EA
518.80	Concrete Deck Repairs	3,079.00	SF
518.81	Full Depth Concrete Deck Repairs	162.00	SF
520.2211	Expansion Joint Modifications - Route 122	1.00	LS
520.2212	Expansion Joint Modifications - Route 197	1.00	LS
520.2213	Expansion Joint Modifications - Gardiner Interchange	1.00	LS
520.23	Asphaltic Plug Joint	44.00	LF
627.681	Temporary 6 Inch Pavement Marking Line, Yellow or White	4,500.00	LF
627.77	Removing Pavement Markings	1,810.00	SF
627.86	Temporary Raised Pavement Markers	120.00	EA
629.05	Hand Labor, Straight Time	80.00	MH
631.10	Air Compressor (including operator)	40.00	HR
631.11	Air Tool (including operator)	80.00	HR
631.171	Truck-small (including operator)	20.00	HR
631.36	Foreman	40.00	HR
652.30	Flashing Arrow Board	2.00	EA
652.312	Type III Barricades	7.00	EA
652.33	Drum	174.00	EA
652.35	Construction Signs	2,066.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	24.00	MH
652.41	Portable-Changable Message Sign	1.00	EA
652.45	Truck Mounted Attenuator	2.00	EA
659.10	Mobilization	1.00	LS