

Maine Turnpike Authority

Contract

2009.01

Pavement Rehabilitation Mile 35.3 to 44.5

Item No.	Description	Quantity	Unit
202.202	Removing Pavement Surface	385,000.00	SY
202.2021	Removing Pavement Surface, Full Depth	1,400.00	SY
202.2026	Removing Pavement Surface - Drainage Path	12,300.00	SF
403.207	Hot Mix Asphalt. 19.0 mm Nominal Maximum Size	635.00	TON
403.210	Hot Mix Asphalt. 9.5 mm Nominal Maximum Size	32,614.00	TON
409.15	Bituminous Tack Coat-Applied	11,781.00	GAL
424.323	Asphalt Rubber Fiber Crack Sealer	20,400.00	LB
427.09	Pavement Joint Repair	1,450.00	LF
459.06	Bituminous Concrete Waterway	39.00	EA
470.08	Berm Drop Off Correction-Grindings	1,200.00	TON
603.155	12 Inch Reinforced Concrete Pipe - Class III	40.00	LF
603.28	Concrete Collar for Reinforced Concrete Pipe	1.00	EA
604.184	Rebuild Catch Basin To Grade - Type II	5.00	EA
604.186	Rebuild Catch Basin To Grade - Type IV	27.00	EA
604.242	Catch Basin Type F-3	3.00	EA
613.319	Erosion Control Blanket	3,260.00	SY
627.712	White or Yellow Pavement Marking Line	193,500.00	LF
627.713	Broken White Pavement Marking Line	183,100.00	LF
627.761	Temporary Pavement Marking Line, Yellow or White	232,000.00	LF
627.77	Removing Existing Pavement Marking	144,900.00	SF
627.802	Temporary Raised Pavement Markers	86,700.00	EA
629.05	Hand Labor, Straight Time	10.00	HR
631.10	Air Compressor (including operator)	5.00	HR
631.11	Air Tool (including operator)	5.00	HR
631.12	All Purpose Excavator (including operator)	20.00	HR
631.17	Truck - large (including operator)	10.00	HR
631.36	Foreman	10.00	HR
652.30	Flashing Arrow	9.00	EA
652.331	Drum (Paid as Lump Sum)	1.00	LS
652.35	Construction Signs	6,500.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.41	Portable-Changable Message Sign	4.00	EA
652.411	Portable-Changable Message Sign - Without Remote	4.00	EA
656.50	Baled Hay, In Place	265.00	EA