



# Maine Turnpike Authority Schedule of Items

## Guardrail Improvements Mile 100.0 to 103.0

Item No.	Description	Quantity	UOM
203.241	Common Borrow, Truck Measure	310	CY
205.51	Widening of Existing Shoulder, Plan Quantity	175	LF
527.301	Energy Absorbing System (CAT)	4	EA
605.13	18 inch Underdrain Type C	150	LF
606.178	Guardrail Beam	200	LF
606.24	Guardrail Type 3d - Single Rail	300	LF
606.2401	Guardrail Type 3d - Double Rail	400	LF
606.2651	Terminal End - Remove and Reset	8	EA
606.277	Terminal End - Trailing End	2	EA
606.353	Delineator Post	16	EA
606.354	Remove and Reset Delineator Post	16	EA
606.3605	Guardrail Remove, Modify and Reset, Single Rail	675	LF
606.3606	Guardrail Remove, Modify and Reset, Double Rail	225	LF
606.3621	Guardrail Adjust, Single Rail	1,000	LF
606.3622	Guardrail Adjust, Double Rail	4,050	LF
606.3631	Guardrail - Remove and Dispose	450	LF
606.471	Single Offset Block - W-Beam	30	EA
606.48	Single Galvanized Steel Post	30	EA
606.754	Widen Shoulder For Guardrail 350 Flared Terminal	8	EA
606.80	Guardrail 350 FLEAT Terminal	8	EA
613.319	Erosion Control Blanket	610	SY
615.07	Loam	165	CY
618.14	Seeding Method Number 2	27	UNIT
619.12	Mulch	27	UNIT
619.1202	Temporary Mulch	1	LS
629.05	Hand Labor, Straight Time	50	HR
631.10	Air Compressor (including operator)	20	HR
631.11	Air Tool (including operator)	20	HR
631.12	All Purpose Excavator (including operator)	40	HR
631.172	Truck - large (including operator)	20	HR
631.36	Foreman	75	HR
645.105	Remove and Stack Sign	2	EA
645.109	Remove and Reset Sign	1	EA
652.30	Flashing Arrow	2	EA
652.34	Cone	500	EA
652.35	Construction Signs	740	SF
652.361	Maintenance of Traffic Control Devices	1	LS
652.45	Truck Mounted Attenuator	1	EA
656.50	Baled Hay, in place	20	EA



## Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
656.60	Temporary Berms	800	LF
656.62	Temporary Slope Drains	250	LF
656.632	30 inch Temporary Silt Fence	1,275	LF
659.10	Mobilization	1	LS